

Update Document – 3/23/2026

- Branford High School
 - o Roof plan uploaded to Exhibit A
 - o Branford has decided not to proceed with the switchgear project as was originally presented. They are putting the project on hold to conduct the appropriate engineering to accommodate behind the meter solar and replacement of their Cogen system. Bidders should assume that the switchgear will be upgraded (at the schools expense) to accommodate future solar.
- Ridgefield High School
 - o No updated structural analysis has been completed for the high school. See previous load letter for initial rooftop project included in Exhibit A. Structural engineering will be included in the awarded EPC contractors scope of work.
- Shad Run Terrace
 - o Re-roof anticipated to start in April 2026. Spec sheet has been uploaded to Exhibit A.
- Ridgebury Elementary School
 - o Original load letter to verify structural capacity prior to solar PV is included in Exhibit A. Additionally, an updated load letter for each site has been uploaded to Exhibit evaluating the structural capacity post-re-roof.
- Rochambeau Apartments
 - o Utility verified load is now 176,146 kWhs. This is the max kWh total for design. This is an increase from the previous figure denoted in Exhibit B, which was 168,276 kWhs.
- Scotland Elementary School
 - o Original load letter to verify structural capacity prior to solar PV is included in Exhibit A. Additionally, an updated load letter for each site has been uploaded to Exhibit evaluating the structural capacity post-re-roof.
 - o Barlow Mountain School
 - PV drawing set for the existing solar project at Barlow Mountain School, as well as an electric bill for the Pool meter at Barlow Mountain (that does not currently have solar tied to it) was previously provided in Exhibit A. The additional bill is tied to the Barlow Mt Pool meter which has a 600amp 120/208v service.
 - As flagged in Exhibit B If Carport +Solar requires a service upgrade, Carport can be tied to Barlow Mountain Elementary School next door.

- Note that a ZREC expired at Barlow Mountain Elementary in late 2025; requiring a 1 year delay before a new submission in the NRES program.
- If the pool meter utility bill is utilized for the project, there should be no delay in submission (as this meter was not previously tied to an expired ZREC contract).
- Due to the requirement in the school carveout that school projects only qualify for the carport adder for 100% carport projects, respondents should provide pricing for carport only design and a hybrid design (rooftop + carport). Required shutdown to take place after school hours.